
3-Unit Fresco Building Stone

Typical Elevation • 25:50:25 Bond • 1/2" Mortar Joints



Guidelines for Installation:

- 1. A FRE23/FRE52 combination will bond with one FRE81.
- 2. Two FRE23s laid on top of each other will bond with one FRE52.
- 3. To maintain the standard ratio of sizes in the wall, FRE81 should be placed approximately 1-1-1/2 feet apart. FRE81 units should not touch each other.
- 4. Vertical joints are generally formed with a combination of three units. Maximum vertical joint is the height of the tallest unit.
- 5. Maximum 3 to 4 foot horizontal joint length depending on wall dimensions.
- 6. Minimum 4" overlap of vertical joints.

Avoid:

- Stepping or stringing together more than
 2 3 units of the same height.
- Creating box patterns in the wall.

Size	Percent	Pieces* per 32 sq. ft.
FRE23	25	17
FRE52	50	17
FRE81	25	6

^{*}One piece equals 2 lineal feet and may be comprised of 2 or more pieces.



General Installation Guidelines

- Arriscraft recommends the use of a Portland cement-lime mortar, proportioned to a 1:1:6 ratio.
- Masonry units should be laid with full head and bed joints except where they are used for weep holes or ventilation.
- Bevel mortar from rear face to prevent protrusion into cavity.
- Prevent excessive mortar droppings by cutting off excess mortar with trowel as the units are laid.
- Butter head joints of unit being placed in wall.
- Place unit to tightly compress mortar.
- Do not re-adjust unit once it has been set in place.
- Tool joints when mortar is thumbprint hard. This timing will depend on the mortar properties and weather conditions.
- Tool joints to a tightly compressed surface to achieve the most weather resistance. Concave tooled
 joints provide the best resistance to moisture penetration.
- After tooling, any excess mortar and dust should be brushed from the masonry surface using a soft bristle brush. Avoid rubbing or pressing the mortar into the units.
- Refer to additional guidelines on the BASIC CARE sheet.

Joint Profile:

